

Abstract Notification dated 7th March 1936.

The attention of the public is hereby invited to the detailed Notification inviting tenders for repairing the Sree Narasimhaswamy Temple at Suggenshalli Magadi Taluk, published on pages 357-359 of Part VI of the *Mysore Gazette*, dated 12th March 1936.

The last date for the receipt of tender is 2 P.M. on 23rd March 1936 and the earnest money to accompany the tender is Rs. 200.

M. A. SRINIVASACHARI,
Executive Engineer.

TUMKUR DIVISION.

Notification dated 16th March 1936.

1. Sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M., on Wednesday the 8th April 1936.
2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Tumkur Division, for each form should be addressed to the Executive Engineer, Tumkur Division, and should be superscribed as 'Tender for constructing Empress Girls' High School at Tumkur.' The name of the tenderer should also be superscribed on the sealed cover.
3. Each tender must be accompanied by a deposit of Rs. 1,500 (in words rupees one thousand five hundred only) in cash as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract (cash amount will not carry any interest).
4. The tenders will be opened in the presence of such contractors who wish to be present on the 8th April 1936. The final acceptance of the tender will rest with the Superintending Engineer, Mysore Circle, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.
5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within 8 days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the Departmental Schedule contract form for the due fulfilment of the contract.
6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.
7. Copies of contract documents, estimates and drawings may be seen at any time at the Executive Engineer's Office, Tumkur Division, on all working days between 11 A.M., and 5 P.M.
8. Specific rates should be given for each item in the Schedule, and the rates should be in rupees, annas and in multiple of three pies and expressed in words and figures. Tenderers offering a percentage reduction on the estimate amount will be rejected.
9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.
10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made the tenders will be liable to rejection.
11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.
12. No reference should be made to the Public Works Department for current schedule of rates.
13. On the event of the tender being submitted by a firm, it must be signed separately and severally by such number thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.
14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer and approved by the Superintending Engineer shall be final and legally binding on the tenderer.
15. The quantities given in the schedule are only approximate and are liable to alterations, omission, deductions, or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those given in the enclosed schedule.
16. The works should be completed and handed over to the Public Works Department by the end of month to be fixed by the Executive Engineer failing which the Executive Engineer may at his discretion levy a penalty, which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed, and handed over.
17. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quantity of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with the application to the Executive Engineer.

19. No claim for damages for delays caused by Officers of the Department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the Departmental Officers will however be considered on the merits of each case.

20. The contract should not be sub-let.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer and the tenderers will pay the hire, etc., on machinery at 25 per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the stores to the date of return to the stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(A) The contractor should at his own cost :—

- (i) Provide rods, stakes, ropes, and labours required in setting out the works.
- (ii) Provide all necessary scaffolding, centering, labour and appliance for hoisting.
- (iii) Provide mortar mill and shed to keep materials under cover and also for workmen.
- (iv) Arrange for protecting work during inclement weather.
- (v) Supply requisite temporary lights, water-cisterns, water-shoots, coverings to masonry tile pieces to steps, sieves, parahs or measures shoring and other requisite protection during the progress of the work.
- (vi) Supply all water required for work and workmen and provide latrines, drainages, etc.
- (vii) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
- (viii) Provide arrangements for pumping and baling from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains slup pits, etc.
- (ix) Wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, and
- (x) Afford facilities to any other parties employed upon the work so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

Note.—(B) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Abstract Estimate for Constructing Empress Girls' High School at Tumkur.

Sl. No.	Items of work	Per	Rate as per estimate	Quantity	Cost	Rate tendered by contractor in	
						Figures	Words
			Rs. a. p.		Rs.		
1	Earthwork excavation for foundation and filling in the foundation and basement, and levelling with watering and tamping complete	C.yd.	0 4 0	412	103		
2	Burnt stone jelly concrete in lime mortar (1:2:4) for foundation and tamping complete ..	C.ft.	0 4 0	2,899	725		
3	Burnt size stone in chunam mortar (1:2) for foundation and basement with through bond stones 6 feet apart in each course, including quoins dressing etc., complete ..	"	0 4 0	7,125	1,781		
4	Burnt bricks in lime mortar (1:2) for superstructure	"	0 4 0	10,288	2,572		
5	Providing and fixing on mortar burnt stone slabs 6" thick with 2 lines dressing and chamfering the edges of exposed surfaces, and rough one line dressing in other places etc., complete	S.ft.	0 0 6	2,749	1,117		
6	Providing and fixing out stone round pillars 3 lines dressed, 12" tapering to 10½" and 12 feet in height, including base and capitals etc., complete as per details shown in plan	Each	45 0 0	4	180		
7	Providing circular pillars with wire cut quadrant bricks 12" tapering to 10½" and about 12 feet in height, including base and capitals and chunam plastering, etc., complete ..	"	15 0 0	16	240		
8	Wire cut brick walls in mortar including plastering with chunam mortar for eud and corner rectangular pillars in verandahs ..	C.ft.	0 12 0	232	174		
9	Providing and fixing first class teakwood doors with frames 5"×4", and panelled shutters 1½" thick, and top ventilators including iron clamps and with necessary brass fittings, etc., complete	S.ft.	1 12 0	520	910		

Sl. No.	Items of work	Per	Rate as per estimate	Quantity	Cost	Rate tendered by contractor in	
						Figures	Words
			R.s a. p.		Rs.		
10	Providing and fixing first class teakwood doors with 4" dia. iron bars, frames 4½"×4", shutters 1½" thick, inside glazed and outside panelled, and with top ventilators including iron clamps and all necessary iron fittings, etc., complete	S.ft.	2 8 0	980	2,450		
11	Supplying and fixing rolled steel girders and joists Tata's tested (B.S.S.) including cost, freight, carting to site, hoisting and fixing, and painting, etc., complete	Cwt.	11 0 0	148.25	..		
12	Roofing with R.C.B. terrace with well burnt first class bricks on edge and 2" cement concrete 1:2:4 on top and sides reinforced with necessary steel bars and bent if necessary, etc., as per specification, also with 3" brick surki concrete, and two courses of flat tiles laid in chunam mortar, and plastering with lime mortar bottom and top and finishing smooth including plaster moulding around along the top of walls at ceilings as per design and white washing, etc., complete	Sqr.	70 0 0	59.24	4,148		
13	Plain cornice work with plaster flutings in between the windows on top as shown in design including backing of terrace and plastering and white washing, etc., complete	R.ft.	0 8 0	477	239		
14	Providing and fixing reinforced cement concrete 3½ feet wide and 3" thick to act as a lovelly cornice (as per design) complete	"	2 4 0	20	45		
15	Constructing parapet walls 2 feet to 2½ feet height and 1½ feet thick with base and plain cornice and with 12 R.C. perforated panels (of 3½'×1'×½' each) including plastering, white and colour washing, etc., complete (as per design)	"	1 6 0	485	667		
16	Plastering with chunam mortar complete	Sqr.	3 0 0	163.70	491		
17	White and colour washing—two coats	"	0 4 6	163.70	46		
18	Flooring with 18 inches square kadappa slabs 1½" thick laid diagonally over 3" stone jelly concrete, and cement pointing, etc., complete	Sqr.	28 0 0	49.34	1,382		
19	Cement pointing to basement including cutting lines	"	4 0 0	9.87	..		
20	Silicate painting two coats, with woodkote paint for outside, and superior Copal varnishing 2 coats inside, complete	"	4 0 0	39.80	159		
21	Boxing double girders of (4½"×1½" section) with brick in cement filling inside and outside and with necessary bolts and nuts including plastering and wire netting around three sides, etc., complete	R.ft.	0 10 0	141	88		
22	Boxing single girders in rooms and halls with side filling wire netting three sides, and plastering, etc., complete (15"×6" section girders)	"	0 8 0	322	161		
23	Providing and fixing cast iron rain water down pipes 4" in diameter, with necessary lead bend at heads, C.I. off-sets, elbows, shoes, clamps, pegs and fittings, etc., including painting complete	"	1 8 0	408	612		
24	Providing a moveable partition between lecture hall and retiring room	L. S.	..	..	..		
25	Carving the name of the building and painting, etc., complete	"	..	..	..		
26	Providing and fixing a flag-staff, etc., complete	"	..	..	..		
27	Providing water connection, etc.	"	..	..	..		
28	Clearing site and levelling ground	"	..	..	..		
29	Constructing necessary drains and sinks in Science Practical Hall	"	..	..	..		
30	Providing road and culvert in front	"	..	..	..		
31	Providing and fixing foundation and opening tablets	"	..	..	..		
32		"	..	..	..		
33	Providing a latrine	"	..	..	..		
34	Constructing a short compound wall with gate pillars and gate, etc.,	"	..	..	..		
35	Sundry and unforeseen works during execution	"	..	..	..		

N.B.—No rate need be given for the lumpsum items.

N. G. KRISHNA IYENGAR,
Executive Engineer.